

पनवेल महानगरपालिका जाहीर निविदा दरपत्रक

आयुक्त, पनवेल महानगरपालिका हद्दीतील नगर रचना योजना पनवेल क्र.१ प्रथम फेरफार अंतिम मधील अं.भु.क्र.३८८ मध्ये Engineering Procurement & Construction (अभियांत्रिकी खरेदी व बांधकाम) तत्वावर बँडमिंटन कोर्टसह बहुउद्देशीय हॉलचे बांधकाम करणे. या कामाचे अंदाजपत्रक बनविण्याकरीता खाली नमूद केलेल्या बाबीकरीता खालील नमूण्यात दर मागविण्यात येत आहे.

अ.क्र.	कामाचे नाव	मुदत
१	पनवेल महानगरपालिका हद्दीतील नगर रचना योजना पनवेल क्र.१ प्रथम फेरफार अंतिम मधील अं.भु.क्र.३८८ मध्ये Engineering Procurement & Construction (अभियांत्रिकी खरेदी व बांधकाम) तत्वावर बँडमिंटन कोर्टसह बहुउद्देशीय हॉलचे बांधकाम करणे.	०५ / ०३ / २०२५ ते ११ / ०३ / २०२५ (७ दिवस)


Specification

Sr. No	DESCRIPTION	Quantity	Unit
	Civil Work		
1.	Providing and Fixing 19mm thick about 600mm wide and 1200 high, approved green Marble urinal partitions machine cut mirror polished on all exposed face and edges polished and semi rounded; fixed to wall including cutting chasing in walls, fixing using required SS pins, clamps, grouted and sealed etc. Complete as per detailed architectural drawing to entire satisfaction of the PM. (Basic rate- @ Rs. 50/- per sft)	319.16	No.
2.	Vinyl Flooring For Table Tennis Hall / Indoor Games Hall / Yoga / Pilates / Zumba Hall / Gym Hall / Basketball & Badminton Court / BOXING/ WRESTLING/MARTIAL ARTS ARENA *Thickness 6.7 MM Vinyl indoor sport floor, EN 14904 (category P1). FIBA & BWF Certified *Weight 3.8 kg/m2 *Width of Roll 2 Meter *Standard Roll Length : 15 ± 10% *Sound Insulation : 22 DB *Having Sports Properties (e.g. Shock absorption & Ball rebound) *Technical Properties (e.g. Dimensional stability, Colour fastness, Chemical & Abrasion resistance *Easy to Clean	508.20	Sqm
3.	Moveable Badminton Poles with Net Moveable Type & having Loose Extra Weight *Made of MS Pipe *Having Provision of Tray System to Keep Extra Loose Weight or Fill it Site *Easy Movement on 2 PU Wheel. *Made of 40mm Round / Square MS Pipe *Epoxy Painted *Garware Tournament quality Net - UV Treated. 1 Year against manufacturing defect for poles (Consumable item e.g. Net will not be covered under warranty)	1.00	Set
4.	Moveable Basketball Poles with Net Made With MS Pipe *Pole will Made 17 CM (6") Round / Square Pipe *Available in 3.2 Mtr Extn. *Acrylic Board Thickness - 25 MM (Imported Quality), Size of Board - 180 cm x 105cm *Height Adjustable from 8' to 10' *Dunking Ring *Quality Net *Epoxy Painted 1 Year against manufacturing defect for poles (Consumable item e.g. Net will not be covered under warranty)	1.00	Pair
5.	Designing, providing, fabricating and fixing in position extruded Alunzioum louvers, as detailed and approved in show shoy drawing (made out of 50mm X 50mm size box section @125mm/c equally placed horizontal as shown		

	in elevation) supported by aluminum framing (tubes/ extruded purpose made sections); aluminium to be polyester powder coated in approved shade and colour. Louvers shall be with required weather proofing, factory-made mechanical junctions with concealed fixing. All items shall be strengthened and lapped as required. Prior to start of work contractor shall submit detailed full scale shop drawings including plan, elevation and detail o fixing with structure for approval of the Project Manager Samples of each item on full scale or smaller scale as directed by the Project Manager shall be submitted for approval. Work shall proceed only on approval of shop drawing. (Measuremen and payment shall be made on the actual finished area on the elevation)	7.00	Sqm
6.	SYSTEM - Design, supply and Installation of aluminium Unitised Structural Glazing system in DGU (6-12-6)MM (i.e 6mm colour reflective high performance glass with 12mm ai gap & 6mm clear glass with Low E coating on surface 3) Having main frame work of mullions (minimum size 2.5 mm thk.) and transomes (minimum size 1.5 mm thk.) of designed extruded sections to withstand a minimum wind pressure of 170 kg./ sqm. and to factor for additional wind pressure on higher floors as per IS standards and fabricated fixed at all levels, elevation & heights. [All Proposed System should be specified by the Vendor along with Structural Stability Repor During submission of Tender] The extruded section shall be finished, with White/Silver PVDF coating and thes same to be approved by architects, of minimum 20 microns. Extruded section shall be of 6063 T6 Alloy or BSH9 conforming to IS 63400. Rate shall include fixing of the main frames to Concrete Steel structure with necessary brackets, clamps, fastening straps, nuts, bolts, rivets, washers and other fastening materials Rate shall include EPDM Neoprene all copings and flashing fire stop seals approved silicon sealant of recommended grade ete complete for a full proof system. No of SIDE OPENABLE PANELS (3.2mx1.5mt) IN GLAZING with locks to be considered as 25 nos	600.00	Sqm
7.	6mm thk Neutro Evolite ET 150 Glass + 12mm gap + 6mm thik Clear Glass with for the DGU panel, SHGC value of 0.42 VLT % 45 and U value of 2.60	60.00	sqm
8.	Providing and fixing the spandrei panel with the Glass wool insulation of 50 mm thick 48 kg/m3 density slab with built in black/grey veil of 0.5 mm firmly held on the GI tray of 1 min thk. The assembly skep Sqm atleast 50mm away from the Glass surface. Weather sealant for sealine the GI tray with Aluminium system.	36.00	sqm
9.	Designing, providing, fabricating and installing ACP Cladding of 4mm thick (0.5mm + 3mm +0.5mm) aluminium composito panels with FR core of approved make, for sizes and panels (based on concept architectural elevation drawings) including required fixtures and fittings of stainless steel (SS 304/316) anchor fasteners, jointing and sealing with M/s. Dow Corning silicon sealant, required fire stops, water drains and gutters and finishing junctions with concrete, stone, timber, aluminium glass etc. all complete. Further include required preparation of shop drawings with structural calculations and getting approva from the Architect and structural consultants, providing samples, mockups, taking actual site measurements and modifying and coordinating with site and fabrication yard, al conforming to international standards etc. complete to the approval of PM. Further the system installed and tested shall be guaranteed for 10 years in approved proforma on stamp paper of appropriate value.	50.00	Sqm
10.	providing and fixing in position Sandwich Roof Sheets panel	1050.67	Sqm
	Electrical Work		

1.	Supplying, installing, testing & commissioning of 6 w LED Spike lightWith Nebula Mini 6W LED, 2700K,3000K,4000K,5700K BA:25° Clear Toughened Glass Product Dim: 101 x 90 x 330mm Similier to KL-4265- Housing - Graphite Grey	23	Each
2.	Supplying, installing, testing & commissioning of 30 W LED, Pelican Fort Mini 30W LED 3000K,4000K,5700K BA:Type III, A9 - Clear Acrylic / A12 - Clear Polycarbonate Product Dim: A9 : Ø425 x 407, A12 : Ø425 x 437mm Similer to KL-5188- Housing - Graphite Grey	17	Each
3.	Supplying, installing, testing & commissioning of Decorative pole ,Pelican Mini Florus Series Product Dim: Single arm 4270mm Similer to KP-5103 including Foundation Bolts M16 X 300 mm- Housing - Graphite Grey	17	Each
4.	Supplying, installing, testing & commissioning of 12 W LED Bollard, Carley Round Bollard 12W LED,2700K,3000K,4000K,6500K, Clear Toughened Glass Product Dim: Ø166 x 970mm Similer to KL-4709- Housing - Graphite Grey	18	Each
5.	Supplying, installing, testing & commissioning of 30 W LED Decorative fixture,Ring Fort Arc Micro 30W LED 2700K,3000K,4000K,5700K, A8 - Translucent Acrylic, A10 - Translucent Acrylic Product Dim: Ø300 x 550mm Similer to KL-4978- Housing - Graphite Grey	20	Each
6.	Supplying, installing, testing & commissioning of Florus Series Product Dim: 3660 mm Similer to KP-4195 including Foundation Bolts M16 X 300 mm Similer to KP-9204- Housing - Graphite Grey	20	Each
7.	Supplying, installing, testing & commissioning of 2x2 60W LED, Aston 2 2 x 60W LED 3000K,4000K,5700K,Amber(25°) BA: 40° Polycarbonate Optical Lens ,Product Dim: 342 x 135 x 245mm Similer to KL-6789- Housing - Graphite Grey	6	Each
8.	Supplying, installing, testing & commissioning of Merlin Lighting Poles Product Dim: 6000 mm Similer to KP-8324 including Foundation Bolts M16 X 500 mm Similer to KP-9205- Housing - Graphite Grey	2	Each
9.	Providing and fixing HT Danger Notice Plate of 250 mm x 200 mm, made of mild steel, at least 2 mm thick, and vitreous enamelled white on both sides and with inscription in singleredcolouronfrontsidesasrequired.	2	Each
10.	Providing and Fixing : Class I, EN12193:Astra Linear Highbay 150W LH24-242-XXX-57-G1 Badminton Court	12	Each

वर नमूद सुचित दर्शविलेल्या बाबींचे पुरवठा करणारे पुरवठादार/दुकानदार/उत्पादक/विक्रेते यांनी नमूद केलेल्या बाबींकरिता असलेले दर स्वतःच्या लेटरहेडवर महापालिकेच्या कार्यालयात अथवा ई-मेल द्वारे pmcbandhkamdept01@gmail.com यावर दिनांक ११ / ०३ / २०२५ पर्यंत पाठवावे ही विनंती, सदर दर हे अंदाजपत्रक तयार करणेसाठी गृहित धरणेत येणार आहेत.



कार्यकारी अभियंता
पनवेल महानगरपालिका

जा.क्र पमपा/बांधकाम/४४२४/प्र.क्र.०३/ ११ / ०३ / २०२५ , दि. ०४ / ०३ / २०२५

प्रत माहितीस्तव — १. माहिती फलक करिता