

पनवेल महानगरपालिका जाहीर निविदा दरपत्रक

आयुक्त, पनवेल महानगरपालिका हद्दीतील विविध ठिकाणी स्मशानभूमी मध्ये चीता संचासाठी वायु प्रदूषण नियंत्रण प्रणाली कार्बनमुक्त मशीनचे पुरवठा करणे. या कामाचे अंदाजपत्रक बनविण्याकरीता खाली नमूद केलेल्या बाबींकरीता खालील नमूण्यात दर मागविण्यात येत आहे.


अ.क्र.	कामाचे नाव	मुदत
१	पनवेल महानगरपालिका हद्दीतील विविध ठिकाणी स्मशानभूमी मध्ये चीता संचासाठी वायु प्रदूषण नियंत्रण प्रणाली कार्बनमुक्त मशीनचे पुरवठा करणे या कामाकरीता दर मागविणेबाबत.	२४/०९/२०२५ ते ३०/०९/२०२५ (७ दिवस)

Specification

Sr. No	Item	Includes	DESCRIPTION	Quantity	Unit	Rate
	SITC of Flaps around the pyre . Below mention MD Steel, HR painted. 3000 x 914 x 5 mm	Flaps around the pyre hood	Metallic flaps around the pyrehood which can be manually lowered to reduce lateral escape of smoke and particulate matter			
			One Flaps around the pyre hood	1	Nos.	
			Two Flaps around the pyre hood	2	Nos.	
			Three Flaps around the pyre hood	3	Nos.	
			Four Flaps around the pyre hood	4	Nos.	
2.	SITC of Air Purification System	A.Dust Vortex System	Separate sout particularte matter higher than and up to PM 10.	1	Unit	
		B.Electrostatic Precipitator (ESP)	Collection of PM10 & PM 2.5 on collector plates-ensuring cleaner emissions.			
		C. Vapox	Removes oils, chemicals, and toxic fumes -cutting down hazardous emissions			
		D.IOTdata Monitoring	Continuous data monitoring system which indicates the inlet gas parameters and outlet parameters, which enables us to check the health of the treatment system, its efficiency and the cleaning indicators.			
		E. ETP	A water treatment system for our unit which ensures no air pollution is converted into water pollution, the water can be reused into the system or for gardening / cleaning purposes.			
		F. High Capacity Blower	A 15,000 CFM blower which will Ensureno pressure dropin the system as well as finest of particles are taken into the cleaning system by the hood.			

3.	SITC of modification of existing site with below mention main ducting inter connecting to hoods, Dampers, Blower/ exhaust fan assembly	H. Modification and installation of the APC on site.	SIT Cofintegrating the Airpurification system with the existing system present at the crematorium.			
			Length for ducting inter connecting to hoods, Dampers, Blower/ exhaust fan assembly	15	Rmt.	
			Length for ducting inter connecting to hoods, Dampers, Blower/ exhaust fan assembly	25	Rmt.	
			Length for ducting inter connecting to hoods, Dampers, Blower/ exhaust fan assembly	35	Rmt.	
			Length for ducting inter connecting to hoods, Dampers, Blower/ exhaust fan assembly	55	Rmt.	
4.	NABL Testing	NABL lab Air sampling and testing	NABL certified testing of inlet & outlet parameters before and after air purification.	1 Pre + 1 Post Treatment Analysis	Job	

वर नमूद सुचित दर्शविलेल्या बाबींचे पुरवठा करणारे पुरवठादार/दुकानदार/उत्पादक/विक्रेते यांनी नमूद केलेल्या बाबींकरीता असलेले दर स्वतःच्या लेटरहेडवर महापालिकेच्या कार्यालयात अथवा ई-मेल द्वारे pmcbandhkamdept01@gmail.com/panvelcorporation@gmail.com यावर दिनांक ३०/०६/२०२५ पर्यंत पाठवावे ही विनंती, सदर दर हे अंदाजपत्रक तयार करणेसाठी गृहित धरणेत येणार आहेत.


कार्यकारी अभियंता
पनवेल महानगरपालिका

जा.क्र पमपा/बांधकाम/४३२५ /प्र.क्र.०८/३६०२/२०२५,
दि.२३/०६/२०२५

प्रत माहितीस्तव — १. माहिती फलक करीता