



पनवेल महानगरपालिका

ता. पनवेल जि. रायगड

कार्यालय- आयुक्त मुख्यालय, २ रा मजला, देवाळे तलावाच्या
समोर, गोखले हॉलच्या शेजारी, पनवेल- ४१०२०६
दुरध्वनी क्र- ०२२-२७४५८०४०/४१/४२
Email Id: panvelcorporation@gmail.com



जा.क्र. पमपा/मल.वि./२२२५/प्र.क्र.०३/३०६/२०२५

दिनांक- २५/०६/२०२५

जाहिर निविदा दरपत्रक सुचना

मा. आयुक्त, पनवेल महानगरपालिका खालील नमूद कामाचे अंदाजपत्रक बनविण्याकरीता खालील बाबींचे दर मागविण्यात येत आहे.

अ.क्र.	कामाचे नाव	कालावधी
	केंद्र शासन पुरस्कृत अमृत २.० अभियानांतर्गत “जल ही अमृत” उपक्रमाद्वारे महानगरपालिकेस प्राप्त निधी अंतर्गत पनवेल येथील १४ द.ल.ली. क्षमतेच्या मलप्रक्रिया केंद्रामध्ये Decanter, Centrifuge and Automatic Gas Chlorination System पुर्नस्थापित करणेबाबत.	दिनांक- २६/०६/२०२५ ते ०३/०७/२०२५ (८ दिवस)

Sr No	Description	Qty	Unit
1	Decanter Assembly and Air Diffusers for C-tech Basin Work Providing, erecting, Testing and commissioning of decanter and diffuser repairs & replace works including removing existing parts of C tech basin as follows- A) Mechanical Works-Overhauling of Decanter Replacement of Worm Shaft-2 nos Replacement of Worm wheel-2 nos Replacement of Bearing set, O-ring set and shaft seal-2 no Replacement of Rubber bellow-2 nos Replacement of Spider-2 nos Minipanel Diffuser with uPVC grid (grid will be replaced if required) – Assuming ~50% of Total quantity-256 nos Diffuser SS clamps, Diffuser O'ring, Diffuser wedges & Diffuser purge assembly PLC CPU-2 nos Ethernet communication Module-3 nos Redundancy Module -2 nos Redundant Power module-1 no Power module cables-2 nos Analog Output Modul-1 no including other charges including Repair & Maintenance of cables, instruments, any consumables required for decanters, repair work related to diffuser air grid, support & any other services/ supply etc	1.00	Nos

2	Centrifuge Providing, erecting, commissioning and testing of Centrifuge capacity of 20.0 m ³ /h (3W+1S) sludge with suspended solids concentration of 0.8 % w/w suspended solids including removing existing assembly. - MOC of all wetted parts will be in SS 316 and casing/housing will be in SS 304 - Solid and Liquid Chutes in MSEP with 22 kW Centrifuge Motor - VFD Module enclosed Control Panel	2.00	Nos
---	---	------	-----

वर नमुद सुचित दर्शविलेल्या बाबींचे पुरवठा करणारे पुरवठादार/दुकानदार/उत्पादक/विक्रेते यांनी नमुद केलेल्या बाबींकरीता असलेले दर स्वतःच्या लेटरहेडवर महापालिकेच्या कार्यालयात अथवा ई-मेल द्वारे panvelmunicipalcorporationswd@gmail.com यावर दि. / /२०२५ पर्यंत पाठवावे ही विनंती, सदर दर हे अंदाजपत्र तयार करणेसाठी गृहित धरणेत येणार आहेत.



शहर अभियंता
पनवेल महानगरपालिका

जा.क्र. पमपा/मल.वि./२२२५/प्र.क्र.०३/३०६ /२०२५, दि. २५ /०८ /२०२५

प्रत माहितीस्तव :-

माहिती फलककरीता