



पनवेल महानगरपालिका

ता. पनवेल, जि. रायगड, पिन नं. ४१० २०६



दूरध्वनी कार्यालय:-०२२-२७४५८०४०,४१,४२

ई-मेल :- panvelcorporation@gmail.com

फॅक्स :- ०२२-२७४५२२३३

वेबसाईट—www.panvelcorporation.com

जा.क्र. पमपा/पापुवि/३५२५/प्र.क्र. /१०५६/२०२५

दि.२५/०९/२०२५

जाहीर निविदा पत्रक

पनवेल महानगरपालिका क्षेत्रातील ओवे तलावातून ओवे कॅम्प व ओवे गावांकरिता पाणी पुरवठा करणेबाबत या कामाचे अंदाजपत्रक बनविण्याकरता खाली नमूद केलेल्या बाबीकरिता खालील नमुन्यात दर मागविण्यात येत आहेत.

अ.क्र	कामाचे नाव	मुदत
1	पनवेल महानगरपालिका क्षेत्रातील ओवे तलावातून ओवे कॅम्प व ओवे गावांकरिता पाणी पुरवठा करणेबाबत.	२६/०९/२०२५ ते ०३/१०/२०२५ (७ दिवस)

Specification

Sr No	Description	Unit	QTY
1	Metallic Pontoon Design, manufacturing of floating pontoon.(Pontoon is suitable for 02 nos. of Submersible pump sets having below duty points. (Flow - 20 LPS = 72 m3/hr. Head- 30 mtr. Motor - 20 HP Pump Qty - 02 nos. Pump will be in client scope) 1.Pontoon Size- 5 x 4 mtr. approx 2.Covering shade on pontoon 3.Chain pulley with trolley of 1T capacity. 4.Safety Railing 5. Paint-Marine paint 6.MOC for pontoon- MS IS 2062 Grade – Br E250 7. Pontoon lifting lugs.	No.	1.00
2	Floating Walkway Metallic Design, manufacturing of floating Walkway. 1.Size - 1 x 2 mtr (Total length of the walkway 100 mtr and width 2 mtr) 2.MOC -MS IS 2062 3.Safety railing 4.Anti-skidding top surface 5.surface painting - PU Coating.	Rmt	100.0
3.	Anchoring and Mooring Supply and Installation of anchoring and mooring. Anchoring and mooring as per Marine Statutory Rules and approvals, necessary bollards, RCC anchors with suitable weight and size, marine chain with suitable size diameter and length etc.	No.	4.00
4.	Header Design, manufacturing, installation of header. Header on pontoon For Discharge pipe inlet-200 DN dia and outlet-200 mm dia.- MS pipe, 300 mm Dia., length -4 mtr approximately. 2 inlet and 1 outlet along with MS flanges hardware and gasket.	No.	1.00

5.	SS Flexible pipe 200 DN Supply and installation of SS flexible Pipe. SS Flexible hose pipe with MS Flange Size-200 mm Length -3 mtr Double braided hose pipe	No.	2.00
6.	SS Flexible pipe 200 DN with MS flange, Length 1 mtr Supply and installation of SS flexible Pipe. SS Flexible hose pipe with MS Flange Size-200 mm Length-1 mtr Single braided hose pipe	No.	9.00
7.	HDPE Pipe 200 DN Supply and installation of HDPE Pipe. MOC-HDPE ,Size-200 DN ,PN 2 welded with 2 stud ends and 2 MS slip flanges inserted UV stabilized raw material.	Rmt	90.00
8.	Installation Services Installation, testing and commissioning of Floating Pontoon Pumping System. Assembly of Pontoon at site along with pump, pump foundation walkway, anchoring and mooring, delivery Pipeline up to shore, valves etc..	No.	1.00
9.	Transportation Transportation of Pontoon, 100 mtr walkway and Anchoring and mooring, header, delivery pipeline from factory (chakan) to site. Loading and unloading, packaging and forwarding transit insurance will be in our scope	No.	1.00
10.	Foundation block Construction of foundation block block Size 6 x 7 mtr approx MOC - PCC Location at shore	No.	1.00
11.	Operation and maintenance Operation and maintenance of Pontoon System for 2 years.	No.	1.00

वर नमूद सूचित दर्शविलेल्या बाबीचे पुरवठा करणारे पुरवठादार/दुकानदार/उत्पादक/विक्रेते/यांनी नमूद केलेल्या बाबीकरता असलेले दर स्वतःच्या लेटरहेडवर महापालिकेच्या कार्यालयात अथवा ई -मेल द्वारे pmcwater2016@gmail.com यावर दिनांक **03/10/2025** पर्यंत पाठवावे हि विनंती, सदर दर हे अंदाजपत्रक तयार करणेसाठी गृहीत धरण्यात येणार आहेत.

Signed by

Sanjay Baraka Katekar

Date: 22-09-2025 15:03:00

शहर अभियंता

पनवेल महानगरपालिका

प्रत माहितीस्तव - 1.प्रसिद्धीकरता.

2.माहिती फलक करिता.